Specification.

All the pipes to be turned and bored of uniform bore and uniform thickness throughout without any belts and of the full specified diameters and to be perfectly free from sand, air holes, flaws and defects of any kind.

2. All pipes to be cast vertically with socket downwards in dry sand moulds.

3. The thickness and weight of the pipes to be as per standard trade practice, suitable for a working head of 500 feet, the least thickness being 7/8".

4. The width and depth of sockets of the pipes to be made according to trade practice.

5. Each pipe to have its weight distinctly painted inside the socket after being dipped in Dr. Augus Smith's solution.

6. A margin in weight of not more than 2½ per cent will be accepted.

7. The 16" diameter pipes to be of an approximate weight of 17 cwts. and the 15" diameter pipes of 15¼ cwts.

8. All pipes to be made in strict accordance with the specification noted above.

Notification dated 8th March 1918.

Notice is hereby given that sealed tenders will be received by the undersigned up to 12 noon of the 1st May 1918, for the supply of about 1,500 gallons of Crude oil or liquid fuel with or without tins required for the use of Nanjangud Pumping Station during the official year 1st July 1918 to 30th June 1919. This quantity is not guaranteed.

2. Tenders should be submitted in printed forms which may be obtained from the undersigned's office.

3. Each tender must be accompanied by a deposit of Rs. 50, as earnest money, and be superscribed "Tenders for the supply of Crude oil for Nanjangud Pumping Station"; in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest with the Executive Engineer, Water-Supply Division, who does not bind himself to accept the lowest or any tender, or assign any reason whatsoever for the rejection of any tender.

5. The rate tendered should include the cost of delivery at Nanjangud Pumping Station and not at godown.

6. The supply should be made in full within two weeks after the orders are placed with the successful tenderer, failing which the unexecuted portion of the order will be cancelled and orders placed elsewhere and the earnest money deposited by the successful competitor forfeited as penalty for the non-execution of the order in full.

7. The name of the successful competitor, whose tender has been accepted will be poste on the notice board of the undersigned's office in the useful course and no enquiries regarding the acceptance or rejection of any tender will receive attention.

8. The successful competitor will be required to execute an agreement bond as per rules.

9. Samples of the oil that each tenderer wishes to supply should accompany the tender.

S. SRINIVASA IYER,
Executive Engineer.

BANGALORE DIVISION.

Dated the 16th March 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 3 P.M., on Tuesday the 26th March 1918, for the supply of the undermentioned pipes required for Maralwady Tank Works.

Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rate at which pipes specified in the list will be supplied; the rate tendered for the pipes shall include cost of delivery at the Stores of the Bangalore Division.

Each tender must be accompanied by a deposit of Rs. 100, in currency or Government Promissory Notes, as earnest money and be superscribed "Tender for the supply of pipes required for Maralwady Tank Works," in default of which tenders will be rejected.

The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

On acceptance of one of the tenders, the earnest money on rejected tenders will be returned. The earnest money of the successful tender will be returned, when the supply is completed satisfactorily.

Pipes should be supplied within a fortnight from the date of receipt of the orders.

Pipes supplied but found not to be of good quality will be rejected and the supplier shall remove the same and shall guarantee to replace the same with fresh ones then and there.

If the successful competitor fail to supply the pipes or replace the rejected pipes in time the same will be purchased elsewhere and difference in cost between the rate tendered and that at which the pipes are purchased will be debited to his accounts.

List of pipes required for Maralwady Tank Works.

Description	Per	Quantity	Rate	Remarks
2" Galvanized iron pipes ...	R. ft.	800		

C. VIJAYARANGAM NAIDU,
Executive Engineer.

TUMKUR DIVISION.

Dated 4th March 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 18th March 1918, for constructing additional rooms to Anglo-Vernacular School at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M., except on Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (350) three hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing additional rooms to Anglo-Vernacular School" at Tumkur, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for extending the Anglo-Vernacular School at Tumkur.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement ...	C. yd.	281
2	Burnt stone in mortar ...	C. ft.	10,874
3	Burnt brick in mortar ...	"	10,175
4	Burnt stone slabs ...	S. ft.	1,700
5	Teakwood doors with panelled shutter and iron works, etc., complete ...	"	208
6	Teakwood windows with iron bars with both panelled and glazed shutters ...	"	299
7	Teakwood ventilators with iron bars and glazed shutters ...	"	105
8	Chunam plastering ...	Sqr.	144·16
9	White and colourwashing ...	"	144·16
10	Providing burnt stone pillars with 7"×7" base and capitals complete ...	No.	28
11	Teakwood work wroght and put up ...	C.ft.	462·00
12	Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete ...	Sqr.	63·06
13	*Ridge* tiles set in mortar ...	R. ft.	132
14	Cornice 1½' deep including plastering ...	"	265
15	Cornice 9" deep including plastering ...	"	84
16	Coping with brick in mortar including plastering ...	"	70
17	Ornamental eave board ...	"	266
18	Zinc sheet for the valley 3' breadth over 1" teak planks ...	S. ft.	75
19	Flooring with Cudapah slabs over 3" concrete bed and cement pointing ...	Sqr.	33·34
20	Chaculate painting ...	"	9·58
21	Wood oiling ...	"	6·02
22	Dwarf wall heavy over gable ends ...	R. ft.	56
23	Dwarf wall light ...	"	40
24	Clearing site and levelling ground ...	Lump sum	rupees
	Old building.		
25	Teakwood panelled doors with iron works, etc., complete ...	S. ft.	28
26	Removing window and inserting door, etc., with repairs ...	No.	1
27	Removing Buttresses and repairs, etc. ...	Lump sum	rupees.